# BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2016-17/RD/WORK_INDENT24258

## APPROVED SCHEDULE - B

**No.CE/BTP/BBMP/E-PMT/20/2016-17, Date: 12.01.2017**

**Improvements to Roads and Drains at 1st Cross Bullet Krishnappa layout in Ward No. 09 (Vidyaranyapura) Vidyaranyapura Sub Division.**

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of KIRAN KRISHNA REDDY | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 1 | 357 | KSRRB 300-47. Scarifying kankar / gravel / metal crust upto 150mm thick with pick axes and disposal of stuff including cost of all labour charges complete as per specifications. | Sqm | 26.0 | Rupees Twenty Six Only |
| 2 | 35 | KSRRB 300 - Excavation for road, drains and similar works KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. | cum | 199.0 | Rupees One Hundred Ninety Nine Only |
| 3 | 60.75 | Removing B.S slab of drain and stacking | Sqm | 65.0 | Rupees Sixty Five Only |
| 4 | 60.75 | Removing and refixing stone slabs of drains and pointing in CM (1:3) | Sqm | 79.0 | Rupees Seventy Nine Only |
| 5 | 53.55 | KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.65cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. | cum | 4850.0 | Rupees Four Thousand Eight Hundred Fifty Only |
| 6 | 28 | KSRB 5-14.2 : Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 5.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2006 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. | Sqm | 880.0 | Rupees Eight Hundred Eighty Only |
| 7 | 8.05 | KSRB 4-1.6 ; Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, ncluding cost of all materials, labour, HOM of machinery, curing complete as per specifications. | cum | 5600.0 | Rupees Five Thousand Six Hundred Only |
| 8 | 42 | KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour complete as per specifications. | Sqm | 310.0 | Rupees Three Hundred Ten Only |
| 9 | 44.63 | Cement concrete pavement.Construction of un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base with OPC cement or any other type as per clause 1051.2.2 design mix M20/M30 , with 25mm and down size graded granite metal coarse aggregates and fine aggregtes , with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008 , mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints including groove cutting charges, joint filler, separation membrane, selant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades as per drawing complete as per specifications. - M20 (at 300Kg per cum | cum | 5400.0 | Rupees Five Thousand Four Hundred Only |
| 10 | 357 | Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift. | Sqm | 95.0 | Rupees Ninety Five Only |

Signature of the contractor



Executive Engineer

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of KIRAN KRISHNA REDDY | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 11 | 83 | Providing granite slabs of selected quality roughly dressed havinf a size of 10 cms thick and fixed in cement mortar (1:6) including fixing curing etc., complete | Sqm | 825.0 | Rupees Eight Hundred Twenty Five Only |
| 12 | 350 | KSRB 5-9 Providing chamfering edges to stone slab 2 5 cms. wide as per specifications. (only chamfered length shall be recorded) | M | 37.0 | Rupees Thirty Seven Only |
| 13 | 83 | KSRB 5-8 2 Providing two line dressing to granite stone slab / granite stone masonry as per specifications. | Sqm | 957.0 | Rupees Nine Hundred Fifty Seven Only |

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

07/04